

Earthwork Cut & Fill Report

to:

GALLERIA II

Block: 36

Lot: 4.11


Township of Evesham

Burlington County, New Jersey

Prepared By:

Menlo Engineering Associates, Inc
261 Cleveland Avenue
Highland Park, New Jersey 08904
T.: 732.846.8585
F.: 732.846.9439

Under the Immediate Supervision of:



William A. Lane
NJPE# 40262

WAL/ab
MEA # 2021.080.02
Dated: March 26, 2025
Revised: January 13, 2026

RECEIVED

JAN 30 2026

P26-04





Grid/Subgrid 1.00/0.50
Section size (Ft) 315.89 x 301.85
Total Work Area (SF) 32,931
Area of Cut (SF) 7,824
Area of Fill (SF) 22,832

Cut Area Threshold 0.01 Ft

Fill Area Threshold 0.01 Ft

All units in Cubic Yards

	Bank	Compacted	Expanded	Comp / Exp (%)
Stripping				
	627	627	627	/
Stripping Total	627	627	627	
Export Stripping		218	218	
Cut				
	368	368	368	/
Cut Total	368	368	368	
Export Cut				
Total Export (Stripping and Cut)		218	218	
Fill				
In Place Fill Required		551		
Stripping and/or Cut Used as Fill	550	550	550	
Import Fill		1		
Topsoil Replacement				
Topsoil Replacement Required		227		
Topsoil Replacement Obtained On Site	227	227	227	
Import Topsoil				



#	Desc	Type	Value	Area (SF)	Material	THK (Ft)	CY	Chg/.1 Ft
▶ 1	 topsoil	STP	0.5	30,114	topsoil	.50	558	112
▶ 4	 r_pave conc	STP	0.67	2,824	pave conc	.67	70	10



#	Desc	Type	Value	Area (SF)	Fill (CY)	Cut (CY) →	Bank	Compacted	Expanded	Chg/.1 Ft
▶ 1	 Topsoil	TSR	0.5	4,317	102		1	1	1	16
▶ 4	 Pave	DPT	0.67	3,333	27		0	0	0	12
▶ 6	 Prop. Swalk	DPT	0.33	3,331	86		0	0	0	12
▶ 8	 Conc Pad	DPT	0.83	140	0		1	1	1	1
▶ 13	 Proposed Building	EL	93.13	12,156	331		0	0	0	45
▶ 17	 Prop. Basin	TSR	0.5	7,933	5		244	244	244	29
▶ 20	 Prop. Basin Sand Bottom	DPT	0.5	1,728	0		122	122	122	6
▶ All				32,938	551		368	368	368	122

